## SQ14 - Cavity - Standby at 40 K

## Sensors and actuators used:

- Temperature: TT664, TT665

- Pressure: PT660 - Flow rate: FT581 - Valve: FV640, FV641

- Control valve: CV601, CV581

- Level: LI660, LI670

## The user chooses:

- Level: LI660Maxi, LI660mini, LI670Maxi, LI670mini

- Temperature: TT665Maxi, TT665mini

Pressure: PT660setpointFlow: FT581setpoint

- Control valve: CV601%opening, CV581%opening

## **Initial conditions:**

- Liquid or Vacuum insert selected
- Sequences from 1 to 3 stopped
- Sequences 10, 12 and 13 stopped
- Sequence 8 in operation

